2603

254

AD 7613

TECHNICAL REPORT NO. 10456


70687384

M4 EXPANSIBLE VAN BODY

PHYSICAL TEST OF

AIRCRAFT TIE-DOWN AND LIFTING EYES

FEBRUARY 1969



Distribution of this document is unlimited.

Reproduced From Best Available Copy

by

C. Blair

MILLER TRAILERS, INC.

CONTRACT NO. DAAE07-68-C-1133

TACOM

DEVELOPMENT & ENGINEERING DIRECTORATE

U.S. ARMY TANK AUTOMOTIVE COMMAND Warren, Michigan

20020813068

The findings in this report are not to be construed as an official Department of the Army position, unless so designated by other authorized documents.

Distribution of this report is Unlimited.

Destroy this report when it is no longer needed. Do not return it to the originator.

#### TECHNICAL REPORT NO. 10456

### M4 EXPANSIBLE VAN BODY

PHYSICAL TEST OF

AIRCRAFT TIE-DOWN AND LIFTING EYES

by

C. Blair Miller Trailers Project Engineer

test held at

Miller Trailers, Inc. Bradenton, Florida

from

3 February 1969 thru 7 February 1969

FEBRUARY 1969

#### **ACKNOWLEDGEMENT**

The program was authorized by the U. S. Army Tank Automotive Command (TACOM), Warren, Michigan under Contract No. DAAE07-68-C-1133. Test Director was Mr. Paul Kelps, project engineer of the Trailer Branch, Development & Engineering Directorate.

#### ABSTRACT

The van body tie-down test was performed on a smooth, level, concrete slab containing a fixed group of permanent anchors set in the concrete, each equipped with a heavy attaching ring. The four anchors used in the test agree closely with the sparing of tie-down rings in the C-124 aircraft.

For the lifting test, sling cables were attached at each end of a longitudinal spreader bar directly over the lifting eyes. Gradually increasing equal pressure was applied through hydraulic actuators. The van floor was loaded with successively greater weights, to simulate 2.0G's.

Subsequently, the body sides were opened to full expanded position, and then re-closed. These operations proceeded smoothly, with no evidence of binding.

### TABLE OF CONTENTS

		·	•	Page	No.
1.	List	of Attendees	••••••		i
2.	Lift	ody Tie-Down and ing Tests Site and Equipment	••••••	•••	2
3.	M4 Body Test				
	3.1	First Test-Using Lift Eyes as Tie-Down Poin	<del>-</del>	•••	3
	3.2	Second Test-Using Life Eyes for Lifting Test Simulate 2.0 G's	_	••• .	4
	3.3	Third Test-Testing Ti Down "U" Bolts in Var Body Skids		/	6
4.	Rest	raint Calculations	••••••	8	8
5.	Appendix		• • • • • • • • • • • •	9	•
		Drawings	••••••	10	) .
		Photographs (Figures	1 thru 37)	14	1
6.	Dist	ribution List		5]	L .

# MILITARY ELECTRORIC CONTROL 333 - 6th AVENUE WEST BRADENTON, FLORIDA 33505

### ATTENDEES:

1. P. KELPS	U. S. ARMY PROJECT ENGINEER, AMSTA-REL
2. J. FOSTER	MARTIN - ORLANDO - M/O
3. F. FISCHER	TECOM
4. C. KNAPPENBERGER	MARTIN - ORLANDO - M/O
5. J. McCAULEY	AMCPM - GPV
6. E. ROACH	MICOM - PPMO
7. J. HAWBLITZEL	MILLER TRAILERS PROJECT MANAGER
8. C. BLAIR	MILLER TRAILERS PROJECT ENGINEER
9. R. B. GLADEN	MILLER TRAILERS VICE PRESIDENT

# MILLER TRAILERS, INC. MILITARY ELECTRONIC DIVISION 333 - 6th AVENUE WEST BRADENTON, FLORIDA 33505

### M4 BODY TIE DOWN AND LIFTING TESTS

PERFORMED AT MILLER TRAILERS, INC. FACILITY AT BRADENTON, FLORIDA, 4, 5, 6 & 7 FEBRUARY 1969. FILE 1053-45

AUTHORIZATION: USATAC WORK DIRECTIVE 1133-313-16

PURPOSE AND PROGRAMMING: AS OUTLINED IN MINUTES OF PRETEST CONFERENCE HELD IO DECEMBER 1968 AT MARTIN-MARIETTA CORPORATION, ORLANDO DIVISION.

TEST SITE AND EQUIPMENT: TEST WAS PERFORMED ON A SMOOTH, LEVEL CONCRETE SLAB, CONTAINING A FIXED GROUP OF PERMANENT ANCHORS SET IN THE CONCRETE, EACH EQUIPPED WITH A HEAVY ATTACHING RING. THE FOUR ANCHORS USED IN THE TEST AGREE CLOSELY WITH THE SPACING OF HEAVY DUTY TIE DOWN RINGS IN THE C-124 AIRCRAFT.

STEEL WIRE ROPES WITH THIMBLES AND APPROPRIATE HOOKS WERE USED TO APPLY THE VARIOUS PULL LOADS TO THE BODY.

POWER WAS APPLIED THROUGH TWO HUDRAULIC ACTUATORS INSERTED IN THE CABLES AT ONE END OF THE BODY. WITH THE BODY FREE TO ROLL ON STEEL ROLLERS, THE PULL IN POWERED CABLES WAS DUPLICATED IN THE PLAIN CABLES AT OPPOSITE END OF BODY.

THE SOURCE OF POWER FOR TIE DOWN TESTS WAS AN ELECTRICALLY DRIVEN HYDRAULIC PUMP, FITTED WITH PRESSURE GAUGE GRADUATED IN 100 P.S.I. INCREMENTS, AND CAPABLE OF REACHING 10,000 P.S.I.

THE HYDRAULIC ACTUATORS USED WERE OF 6 INCHES INSIDE DIAMETER, HAVING A 7 INCH STROKE AND 2 INCH DIAMETER PISTON ROD. SINCE THE POWER WAS APPLIED ON THE ROD SIDE OF THE PISTON, THE EFFECTIVE AREA UNDER PRESSURE WAS .7854  $(6)^2$ -.7854(2) $^2$ =25.13 SQ.IN.

THE LIFTING TEST WAS PERFORMED WITH A SINGLE PORTABLE CRANE, WITH THE LIFTING HOOK ATTACHED AT THE CENTER OF A LONGITUDINAL SPREADER BAR. THE SLING CABLES DESCRIBED UNDER "SECOND TEST" WERE ATTACHED AT EACH END OF THE SPREADER BAR, DIRECTLY OVER THE LIFTING EYES ON THE VAN BODY.

MILLER TRAILE. S. INC.
MILITARY ELECTRONIC DIVISION
333 - 6th AVENUE WEST
BRADENTON, FLORIDA 33505

M4 BODY TEST

3

4 FEBRUARY 1969 - FIRST TEST, USING LIFTING EYES AS TIE DOWN POINTS, PER MILLER DRAW-ING 1052-32-100.

BODY WAS LOCATED ON TEST SITE AND SUPPORTED ON STEEL ROLLERS. WITH SPECIAL OUTBOARD ADAPTERS MOUNTED IN PLACE OF THE FORWARD LIFTING EYES, STEEL CABLES WERE RIGGED TO PERMANENT ANCHORS IN THE CONCRETE SLAB, WITH A HYDRAULIC ACTUATOR INCORPORATED IN EACH OF THE TWO CABLES FROM THE FORWARD EYES. THE ANGULARITY OF BOTH FORWARD AND REAR CABLES WAS 35 DEGREES FROM VERTICAL, DICTATED BY THE LOCATION OF PERMANENT ANCHORS.

GRADUALLY INCREASING EQUAL PRESSURE WAS APPLIED SIMULTANEOUSLY TO THE HYDRAULIC ACTUATORS, UNTIL A PRESSURE OF 400 P.S.I. WAS REACHED.

INSPECTION OF EACH EYE SHOWED DISTRESS ONLY AT THE L.H. REAR, WHERE THE UPPER EDGE OF THE MOUNTING FLANGE SEPARATED FROM THE BODY SKIN APPROXIMATELY 1/16 INCH. ALL THREE BOLTS HOLDING THIS EYE IN PLACE WERE FOUND TO BE LOOSE, WITH A BROKEN LOCKWASHER AT ONE. THESE BOLTS ARE MADE FROM VERY SOFT STEEL, WITH NO HEAD MARKINGS. SINCE THE SEATING FACE OF ONE BOLT HAD BEEN DESTROYED, IT WAS REPLACED WITH A GRADE 5 BOLT, AND ALL BOLTS AND NUTS AT EACH LIFTING EYE WERE TORQUED TO 100 FT. LBS. THE TEST WAS THEN REPEATED, WITH NO FURTHER FAILURES EVIDENT.

SINCE THE HYDRAULIC ACTUATORS USED HAVE A NET PISTON AREA OF 25.13 SQ. IN., THE 400 P.S.I. USED APPLIED A PULL OF 10,050 LBS. AT EACH FRONT CABLE. WITH EQUAL ANGULARITY AND THE BODY RESTING ON ROLLERS, THE SAME PULL WAS TRANSFERRED TO THE REAR. AT THE 35 DEGREE ANGLE, THE 10,000 LB. PULL HAS AN 8190 LB. VERTICAL COMPONENT, AND 5735 LB. HORIZONTAL COMPONENT.

## MILLER TRAILERS, INC. MILITARY ELECTRONIC DIVISION 333 - 6th AVENUE WEST BRADENTON, FLORIDA 33505

M4 BODY TEST (CONTINUED)

5 FEBRUARY 1969 - SECOND TEST, USING LIFTING EYES FOR LIFTING TEST, TO SIMULATE 2.0 G'S. SCALE WEIGHT OF EMPTY BODY WITH ADAPTER 9,370 LBS. REFERENCE: MILLER DRAWING NO. 1053-45

THE HOOK OF A PORTABLE LIFTING CRANE, WITH A LONGITUDINAL SPREADER BAR, WAS POSITIONED OVER THE CENTER OF THE VAN BODY. CABLE SLINGS WERE RIGGED FROM EACH END OF THE SPREADER BAR TO THE FORWARD AND REAR LIFTING EYES ON THE BODY.

THE INDIVIDUAL SLINGS AT THE FRONT WERE AT AN ANGLE OF 32 DEGREES FROM VERTICAL, AND AT THE REAR, THE ANGLE FROM VERTICAL WAS 18 DEGREES, 30 MINUTES.

AN INITIAL LOAD OF 4158 LBS. WAS PLACED ON THE VAN BODY FLOOR, COVERING APPROXIMATELY 48 INCHES CENTRALLY OF THE FLOOR WIDTH, AND EVENLY DISTRIBUTED LONGITUDINALLY. THIS GROSS LOAD WAS LIFTED WITH NO SIGN OF DISTRESS.

TOTAL LOAD WAS THEN INCREASED TO 6158 LBS., AND AGAIN LIFTED. THERE WAS NO EVIDENCE OF PISTRESS.

WITH TOTAL LOAD OF 8158 LBS., COVERING FULL WIDTH OF VAN FLOOR, INSPECTION AFTER LIFT SHOWED A SLIGHT SEPARATION AT THE LOWER HALF OF SKIN VERTICAL LAPS, APPROXIMATELY 1/32 INCH, ON ROADSIDE OF BODY, AND A SLIGHT DEFORMATION OF THE HONEY COMB STRUCTURE IMMEDIATELY UNDER THE FLOOR PAN.

WHEN THE LOAD WAS INCREASED TO 10,158 LBS., AND LIFTED, A FURTHER INCREASE WAS NOTED IN THE SKIN LAP SEPARATION, AS WELL AS A SLIGHT SAG AT THE CENTER OF THE WHOLE STRUCTURE. THIS SAG DISAPPEARED WHEN THE LOAD WAS REMOVED.

AT THIS POINT, IT WAS DECIDED BY ATTENDING USATAC PERSONNEL THAT ONLY 1,500 LBS. ADDITIONAL WEIGHT WOULD BE ADDED, BRING THE TOTAL FLOOR WEIGHT TO 11,658 LBS., IN ORDER TO AVOID PERMANENT DAMAGE TO THE BODY WHICH WAS NOT DESIGNED TO CARRY SO EXCESSIVE A FLOOR LOAD.

WHEN LIFTED WITH 11,658 LBS. LOAD, THERE WAS NO FURTHER EVIDENCE OF PISTRESS, AND THE TEST ENDED WITH THIS LIFT.

MILLER TRAIL

MILITARY ELECTRONIC DIVISION

333 - 6th AVENUE WEST

BRADENTON, FLORIDA 33505

M4 BODY TEST (CONTINUED)

- 5 FEBRUARY 1969 -

BASED ON THE 11,680 LBS. GIVEN IN MINUTES OF PRE-TEST MEETING 10 DECEMBER 1968 AS THE WEIGHT OF LOADED VAN BODY WITH ADAPTER, THE FINAL LIFTED WEIGHT REPRESENTS 9.379 + 11,658 = 1.8 G'S, WHICH WAS DEEMED SUFFICIENT BY USATAC PERSONNEL.

SUBSEQUENTLY, THE BODY SIDES WERE OPENED TO THE FULL EXPANDED POSITION, AND WERE THEN RE-CLOSED. THESE OPERATIONS PROCEEDED SMOOTHLY AND NORMALLY, WITH NO EVIDENCE OF BINDING.

#### MILLER TRAILERS, INC.

MILITARY ELECTRONIC DIVISION 333 - 6th AVENUE WEST BRADENTON, FLORIDA 33505

#### M4 BODY TEST

4, 5, 6, & 7 FEBRUARY 1969 - THIRD TEST: TESTING TIE DOWN
"U" BOLTS IN VAN BODY SKIDS,
SIMULATING AIRCRAFT LOADING
TIE DOWN. EACH "U" BOLT TO
BE LOADED TO 20,000 LBS.
CABLE TENSION. REFERENCE
MILLER DRAWING 1052-32-101

BODY WAS LOCATED ON TEST SITE, SUPPORTED ON ROLLERS, IN SAME POSITION AS FOR FIRST TEST. IN THIS POSITION, THE ANGLE OF PULL ON THE END RESTRAINING CABLES VERY CLOSELY APPROXIMATES THE SITUATION IN THE C-124 AIRCRAFT, BUT IS ONLY 15°-30' AT THE CENTER "U" BOLT.

THE FIRST PHASE OF THIS TEST INVOLVED THE FOUR END "U" BOLTS, TWO AT FRONT AND TWO AT REAR, WITH PLAIN CABLES ATTACHED AT FRONT AND HYDRAULIC ACTUATORS IN THE REAR CABLES. WHEN THE TEST LOAD WAS APPLIED AT EACH ACTUATOR, THE TWO FRONT "U" BOLTS SHOWED NO SIGNS OF DISTRESS, BEYOND A SLIGHT BENDING DEFORMATION IN THE "U" CONFIGURATION.

HOWEVER, BOTH REAR "U" BOLTS SHOWED EXCESSIVE BENDING, AND APPROXIMATELY 3/16" "PULL OUT" OF THE WEB OF THE SKID RAIL CHANNEL, ALSO BENDING OF THE 3/16" THICK REINFORCING PLATE. UNDER THE NUTS AT INNER ENDS OF THE "U" BOLT LEGS. INVESTIGATION SHOWED THAT THE BODY OF THE HYDRAULIC ACTUATOR WAS INTERFERING WITH THE ADAPTER BRACKETS, FORMING A LEVERAGE SYSTEM WHICH GENERATED A GREAT AMOUNT OF TRANSVERSE LOAD AT THE "U" BOLT, THUS ACCOUNTING FOR THE "PULL OUT" OF THE CHANNEL WEB, AS WELL AS EXCESSIVE DEFORMATION OF THE INNER PLATE.

AT THIS POINT TESTING WAS HALTED, AND THE DEFORMED CHANNEL WEBS AND REINFORCING PLATES WERE HAMMERED BACK TO THEIR ORIGINAL FLAT CONDITION. THE REAR "U" BOLTS WERE REMOVED AND CHECKED FOR HARDNESS ON A ROCKWELL HARDNESS TESTER, WHICH SHOWED THE "U" BOLT HARDNESS TO BE IN THE RANGE OF RC-33 TO 34. THE "U" BOLTS WERE THEN REWORKED COLD TO THEIR ORIGINAL SHARE, AND REASSEMBLED TO THE VAN.

DUE TO FAILURE OF ONE OF THE HYDRAULIC ACTUATORS, IT WAS NECESSARY TO CONTINUE THE TEST WITH THE ONE REMAINING UNIT. THIS WAS RERIGGED AT THE APPROXIMATE CENTER OF THE CABLE FROM ROADSIDE REAR "U" BOLT, TO ELIMINATE ADAPTER BRACKET INTERFERENCE, AND A BALANCING

MILLER TRAIL.

MILITARY ELECTRONIC DIVISION

333 - 6th AVENUE WEST

BRADENTON, FLORIDA 33505-

M4 BODY TEST (CONTINUED)

4, 5, 6, & 7 FEBRUARY 1969

OPPOSITE CABLE WAS CONNECTED AT THE CURBSIDE CENTER "U" BOLT, LEADING FORWARD TO A PERMANENT ANCHOR.

800 PLUS P.S.I. PRESSURE WAS APPLIED AT THE ACTUATOR, WHICH DEVELOPED A 20,000 LB. PULL AT BOTH THE ROADSIDE REAR AND CURBSIDE CENTER "U" BOLTS. BEYOND A SLIGHT BENDING IN THE "U" BOLTS THEMSELVES, NO FAILURES WERE EVIDENT, AND THE TEST WAS CONSIDERED PASSED. ATTENDING USATAC PERSONNEL WAIVED THE NECESSITY OF TESTING THE ROADSIDE CENTER "U" BOLT.

#### **RECOMMENDATIONS:**

- I. THAT NO M4 VAN BODY SHALL PASS FINAL INSPECTION UNLESS SAE GRADE 5 BOLTS AS SPECIFIED ON ORDNANCE DRAWINGS, PROPERLY TORQUED, ARE USED TO MOUNT THE FOUR LIFTING EYES.
- 2. THAT THE REINFORCING PLATES ON INSIDE OF SKID CHANNELS AT EACH "U" BOLT BE INCREASED IN THICKNESS, LENGTH AND WIDTH, WITH EACH END WELDED TO THE CHANNEL WEB.

SALE DATE 24 VAN 69 SUBJECT M4 BODY

RESTRAINT CALCS, FOR TIE DOWN PROPOSAL IN C-124 AIRCRAFT

333 - 681 AVENUE, WEST

BRADENTON, FLORIDA 33505 I. FORWARD RESTRAINT:

ASSUME ALL TIE CHAINS AT 25-50 FROM CENTERLINE THIS IS THE MEAN OF 3 ANGLES RANGING BETWEEN 25 4 27-30'.

ASSUME 8 G'S RESTRAINT REQUIRED 8(11,680) = 93,540 TOTAL RESTRAINT REOP. 93,540 ÷6 = 15,590 RESTRAINT EACH TIE ( | TO ¢)

15,590 = 17,300 LBS. ACTUAL TENSION EACH TIE

2. REARWARD RESTRAINT: - 8 G'S ASSUME ALL TIE CHAINS AT 28-40 FROM CENTERLINE THIS IS MEAN OF 3 ANGLES RANGING FROM 25-30 TO 33"

 $\frac{15,590 (AS ABOVE)}{COS 28°-40°} = 17,750 ACTUAL TENSION EACHTIE AT 8 G'S.$ 


3. LATERAL RESTRAINT: ASSUME 1.5 G'S REQD. ASSUME ALL TIE CHAINS AT 27-45. THIS ISMEAN OF SIX ANGLES RANGING FROM 25°TO 33°


1.5 (11,680) = 17,520 LBS, TOTAL RESTRAINT REQD.


17,520÷6 = 2,920 LBS. RESTRAINT EACH TIE (上TO E)


= 6,250 LBS. ACTUAL TENSION EACHTIE AT 1.5 G'S


APPENDIX






































MILLER TRAILERS, INC.
MILITARY ELECTRONIC DIVISION
333 · 6th AVENUE WEST
BRADENTON FLORIDA 33505




M4 BODY TEST

10,000lbs. UPPER TIE TEST AT DOWN

### MILLER TRAILERS, INC.


MILITARY ELECTRONIC DIVISION 333 - 6th Avenue, West Bradenton, Florida 33505



M4 BODY TEST

UPPER TIE DOWN TEST AT 10,000lbs.

# MILLER TRAILERS, INC. MILITARY ELECTRONIC DIVISION 333 - 6th AVENUE WEST BRADENTON FLORIDA 33505




MA BODY TEST

INSPECTION OF UPPER TIE

DOWNS AND ROOF AFTER

10,0001b. TEST.

# MILLER TRAILERS, INC. MILITARY ELECTRONIC DIVISION 333 - 6th AVENUE WEST BRADENTON FLORIDA 33505



M4 BODY TEST

BOLT REMOVED AFTER UPPER
TIE DOWN TEST. THIS BOLT
WAS NOT A GRADE 5 BOLT.
NO VISIBLE DAMAGE.

### MILLER TRAILERS, INC.


MILITARY ELECTRONIC DIVISION 333 - 6th AVENUE WEST BRADENTON, FLORIDA 33505



M4 BODY TEST

II,658LB. LOAD ADDED TO EMPTY VAN FOR LIFT TEST.


MILLER TRAILERS, INC.
MILITARY ELECTRONIC DIVISION
333 - 6th AVENUE WEST
BRADENTON, FLORIDA 33505



M4 BODY TEST

LIFTING TEST AT 11,658LB. LOAD.


# MILLER TRAILERS, ING. MILITARY ELECTRONIC DIVISION 333 - 6th AVENUE WEST BRADENTON, FLORIDA 33505



M4 BODY TEST

SKIN SEPARATION AFTER 11,658LB.
LIFT TEST.


MILITARY ELECTRONIC DIVISION 333 - 6th AVENUE WEST BRADENTON, FLORIDA 33505



M4 BODY TEST

CLOSE UP, SKIN SEPARATION AFTER 11,658LB.
LIFT TEST.

MILITARY ELECTRONIC DIVISION 333 - 6th AVENUE WEST BRADENTON, FLORIDA 33505



M4 BODY TEST

SKIN WARP DOWN LEFT SIDE AFTER 11,658LB. LIFT TEST.

# MILLER TRAILERS, INC. MILITARY ELECTRONIC DIVISION 333 - 6th AVENUE WEST BRADENTON FLORIDA 33505



M4 BODY TEST

LOWER TIE DOWN TEST AT 20,000lbs.


MILLER TRAILERS, INC.
MILITARY ELECTRONIC DIVISION 333 - 6th AVENUE WEST BRADENTON, FLORIDA 33505



BODY TEST M4

LOWER TIE DOWN TEST AT 20,000lbs.


# MILLER TRAILERS, INC. MILITARY ELECTRONIC DIVISION 333 - 6th AVENUE. WEST BRADENTON. FLORIDA 33505



M4 BODY TEST

LOWER TIE DOWN TEST AT 20,000lbs.

MILITARY ELECTRONIC DIVISION 333 - 6th AVENUE WEST BRADENTON FLORIDA 33505




M4 BODY TEST

GAUGE READING AT MAXIMUM

FOR 20,0001b, LOWER TIE

DOWN TEST.

MILITARY ELECTRONIC DIVISION 333 - 6th Avenue West Bradenton, Florida 33505




M4 BODY TEST

RIGHT FRONT LOWER TIE

DOWN AFTER 20,0001b.TEST

# MILLER TRAILERS, INC. MILITARY ELECTRONIC DIVISION 333 - 6th AVENUE. WEST BRADENTON, FLORIDA 33505




M4 BODY TEST

LEFT REAR LOWER TIE

DOWN AFTER 20,000lb. TEST.


# MILLER TRAILERS, INC. MILITARY ELECTRONIC DIVISION 333 - 6th AVENUE WEST BRADENTON, FLORIDA 33505



M4 BODY TEST

BACK PLATE ON RIGHT
FRONT LOWER TIE DOWN
AFTER 20,0001b. TEST.


# MILLER TRAILERS, INC. MILITARY ELECTRONIC DIVISION 333 - 6th AVENUE WEST BRADENTON, FLORIDA 33505



M4 BODY TEST

LOWER TIE DOWN, RIGHT CENTER, 20,000lb. TEST.


MILITARY ELECTRONIC DIVISION 333 - 6th Avenue West Bradenton, Florida 33505



MA BODY TEST

LOWER TIE DOWN, RIGHT CENTER, AFTER 20,0001b.


# MILLER TRAILERS, INC. MILITARY ELECTRONIC DIVISION 333 • 6th AVENUE WEST BRADENTON, FLORIDA 33505



M4 BODY TEST

LOWER TIE DOWN, RIGHT CENTER, AFTER 20,000lb.


MILLER TRAILERS, INC.
MILITARY ELECTRONIC DIVISION
333 - 6th AVENUE, WEST
BRADENTON, FLORIDA 33505



M4 BODY TEST

EXPANDED BODY AFTER ALL TESTS WERE COMPLETED.


MILITARY ELECTRONIC DIVISION 333 - 6th Avenue, West Bradenton, Florida 33505



M4 BODY TEST

BODY EXPANDED AFTER ALL TESTS WERE COMPLETED.


## MILLER TRAILERS, INC. MILITARY ELECTRONIC DIVISION 333 - 6th AVENUE, WEST BRADENTON, FLORIDA 33505



M4 BODY TEST

BODY CLOSED AFTER THE
BODY HAD BEEN EXPANDED
AFTER ALL TESTS HAD
BEEN COMPLETED.


MILLER TRAILERS, INC.
MILITARY ELECTRONIC DIVISION
333 - 6th AVENUE WEST BRADENTON, FLORIDA 33505



M4 BODY TEST

BODY CLOSED AFTER THE BODY HAD BEEN EXPANDED AFTER ALL TESTS HAD BEEN COMPLETED.

MILITARY ELECTRONIC DIVISION 333 - 6th AVENUE WEST BRADENTON, FLORIDA 33505



M4 BODY TEST


RIGHT REAR LOWER TIE DOWN SHOWING DISTRESS

AFTER FIRST ATTEMPT TO REACH 20,000LB. TEST

PULL, DURING WHICH ACTUATOR INTERFERED WITH

ADAPTER BRACKET. (BRACKET NOT SHOWN)


MILITARY ELECTRONIC DIVISION 333 - 6th AVENUE WEST BRADENTON, FLORIDA 33505



M4 BODY TEST

DISTORTION IN RIGHT REAR LOWER TIE DOWN AFTER FIRST ATTEMPT TO REACH 20,000LB.
TEST PULL.


MILITARY ELECTRONIC DIVISION 333 - 6th AVENUE WEST BRADENTON, FLORIDA 33505



M4 BODY TEST

DISTORTION IN LEFT REAR LOWER TIE DOWN AFTER FIRST ATTEMPT TO REACH 20,000LB. TEST PULL.

MILITARY ELECTRONIC DIVISION 333 - 6th AVENUE WEST BRADENTON, FLORIDA 33505



M4 VAN BODY ON SCALES. TOTAL WEIGHT OF VAN WITH ADAPTER WAS 9,370LBS. THIS WEIGHT INCLUDED 100' CABLE, CABLEREEL, 2 FIRE BOTTLES AND WOOD SPACERS. LIFTING SLINGS WERE REMOVED.

## DISTRIBUTION LIST

				NO. OI	copies
Commanding	General				
USArmy Tan!	k Automotiv	e Command			
ATTN:	AMSTA-REL		• • • • •		· (2)
ATTN:	AMCPM-GPV,				
	AMSTA-LP		• • • • • •		
ATTN:	AMSTA-BAM,				
	AMSTA-BSL		• • • • • •		
Commander					
Defense Do	cumentation	Center			.•
ATTN: DDC	-IR				
Cameron Sta	ation				
Aelxandria	, <b>V</b> irginia	22314	•••••	•••••	(20)
Commander			,		
USArmy Mun:	itions Comm	and			
ATTN: AMC	PM-PE-EG, M	r. E. Roac	h		
Redstone A					
Philadelph:	ia, Pennsyl	wania 191	37		(2)

Security Classification						
DOCUMENT CONT	ROL DATA - R	& D				
(Security classification of title, body of abstract and indexing	annotation must be e	nteted when the	overall report is classified)			
1. ORIGINATING ACTIVITY (Corporate author)		28. REPORT SECURITY CLASSIFICATION				
Miller Trailer, Inc.	•	UNCLASSIFIED				
Bradenton, Florida		25. GROUP				
3. REPORT TITLE	<del> </del>	L				
M4 Expansible Van Body Physical Tes	st of Airc	raft Tie	-Down and			
Lifting Eyes						
direing ayou						
4. DESCRIPTIVE NOTES (Type of report and inclusive dates)						
Final Technical Report - 3-7 Februa	arv 1969					
5. AUTHOR(5) (First name, middle initial, last name)						
Paul Kelps						
raul kelps						
8. REPORT DATE	78. TOTAL NO. O	PAGES	76. NO. OF REFS			
February 1969	49					
BB. CONTRACT OR GRANT NO.	Se. ORIGINATOR'S	REPORT NUME	DER(S)			
DAAE-07-68-C-1133			•			
b. PROJECT NO.	USATACOM RPT # 10456					
· . c.						
<b>.</b> .	this report)	(1 NO(S) (Ality of	her numbers that may be assigned			
d.						
10. DISTRIBUTION STATEMENT	1					
Distribution of this document is Ur	ha+imifa					
Distribution of this document is of	IIIIII Ced.					
11. SUPPLEMENTARY NOTES	12. SPONSORING MILITARY ACTIVITY					
	Army Tank Automotive Command					
	D & E Directorate					
	Warren, I	Michigan	48090			
13. ABSTRACT						
The van body tie-down test was perf	ormed on a	a smooth	, level, concrete			
slab containing a fixed group of pe	ermanent a	nchors s	et in the con-			
crete, each equipped with a heavy a	ttaching :	ring. T	he four anchors			
used in the test agree closely with	_	-				
the C-124 aircraft.	. Circ bput.	ing of c	re down rrings rn			
the C-124 dilcidit.						
For the lifting test, sling cables						
longitudinal spreader bar directly						
increasing equal pressure was appli	ed through	h hydrau	lic actuators.			
The van floor was loaded with succe	essively gr	reater w	eights, to sim-			
ulate 2.0G's.						
			•			
Subsequently, the body sides were o	nened to	Full eva	anded nosition			
and then re-closed. These operation						
	ms broceed	rea smoo	cury, with no			
evidence of binding.	•					

DD FORM 1473

UNCLASSIFIED

Security Classification

### UNCLASSIFIED

14.	ssification			LINK A		LINKB		LINK C	
• • •	KEY WORDS	, to	3 "	ROLE	WT	ROLE	WT	ROLE	WT
			<b></b>						
Cargo Vehicle		. 70	÷						
		• •							
Van Body				1.				i	
Lifting Eyes				ļ	]				
mia Darm mant									
Tie-Down Test	•		•	ļ					
Lifting Test	•			•					,
Directing 1000	* 1								
<i>y</i>	•								
				<b>!</b> .				1	
								Ī	
				'					
				ļ. 			ļ		
				· ·		ļ			
					·	1		Ì	
						}	1	1	
•.	ents V						1		
·						İ	i		
				l j	<u> </u>		-	1	
					.	.	1	İ	
	,				ļ		. 1		
					Í				
	•								
					.	.			
							ĺ		
				l				1	4
				·					•
•	•						ł		٠.
•				·	-				,
						ľ	0	f	
				, ,,,∤			•		•
	•			· ·	.		,	· .	
							1	. }	
				1					
			j	1				j	
				·			•	1.	
			l	1	- 1		. 1	.	

UNCLASSIFIED

Security Classification